Northeast Radiant Technology, LLC. Plan For Job #0304-05 Gordon McAlister Radiant Floor Heating System and Propex Plumbing System Contruction Copy

Contents

Revision History

Page	Description	Date	Rev.#	• Page(s)	Description
1	Contents and Contact Info	4/16/04	Orig.	1-4	Construction Copy #1: Distribution and Propex Only
2	Schedules, Specs, Installation Notes				
3	Slab Tubing Layout, Key To Symbols				
4	1st + 2nd Fl. Layouts, H.A. Schedule				
5	Propex Plumbing System Details				
6	Controls and Wiring diagrams				

Job Owner/Installer:

Gordon McAlister 360 South Pleasant Ave. Ridgewood, NJ 07450 ph 201-444-9647

Please note: These plans are to be used with any and all instructions and manuals that accompany parts to the job site. Frequently these manuals will include more specific information than we have included in our job design notes.

site conditions may force changes from the planned installation; changes should be reviewed if possible by Northeast Radiant Technology for impact on the overall system design. Changes to the scope of the job can potentially invalidate this plan.





Contruction Copy

-Read through the Wirsbo Installation Manual

sources for more than 30 days.

order to help prevent tearing.

flooring, etc. are made.

Installation manual section 9.

manual.

plunger.

completed.

Approx.

-Prior to installation, open all boxes and verify that parts received

match up to the parts list included with these drawings! Number

loop schedule on this page. Make sure to cut all runs from the

the Tubing boxes as indicated on the Cut List on the

Do not allow PEX to remain exposed to direct sunlight or other UV

-When tight loop bends are required, it is acceptable to make the bend wider than the on-center of the runs to simplify installation.

Allowing tubing to "bow out" at the loop head will not affect

performance. If a kink occurs, using a heat gun to reform the

valves on the loops are easily accessible. Typically the return

order on each manifold! Black caps on balancing valves

manifold is against the wall with its tubing running behind the

tubing is recommended: see page 14 of the Wirsbo Installation

-Manifolds should be installed so all propex fittings and balancing

valveless supply manifold, which is mounted below and in front of

the return manifold. Make sure to label each loop as you attach it

to the manifold and attach the supply and return ends in the same

should be affixed loosely so they do not push down the

-Threaded connections with gaskets or O-rings do NOT require

thread tape or sealing compound! O-rings should be moistened

with water or saliva before attempting to seal the connection, in

- Pressure Testing will be done directly on the manifolds using

Wirsbo Pressure Test Kits. Directions for pressure testing are

included in the Wirsbo installation manual Section 9. System

should be under pressure before the concrete pour and should

remain under pressure until all floor penetrations for wall plates,

-Purging the entire system of air is required after installation is

-Balancing loops are required; Use the initial settings listed under

the Loop Schedule. Instructions for balancing are in the Wirsbo

-RTU and thermostat locations are approximate. Run 18-2 wire

from the controls location to the RTU locations.

correct rolls of tubing to prevent unnecessary tubing waste!

-PEX is sensitive to prolonged exposure to UV Radiation.

-Use a tubing cutter to ensure smooth tubing cuts.

Performance Specs

Rm.	Room Name	Room	Wall	Ceil.	SbFl.	Win	ACH	Flooring	Floor	BTUs	Water	
#		Temp	R.	R.	R.	R.		Туре	R.	S.F./HR	Temp	
1	Garage	70	24	5*	10	3	.3	None	0	15	80	
2	Base Bath	70	24	5*	10	3	.3	Tile	1.4	13	85	
3	Wet Bar	70	24	5*	10	3	.3	Tile	1.4	16	87	
4	Family Room	70	24	5*	10	3	.3	Carpet	2	12	105	
5	M. Bed	70	11	0*	5*	3	.75	Larch Pine	1.8	30	140*	
6	M. Bath	70	11	0*	5*	3	.75	Larch Pine	1.8	30	140*	
7	Entry	70	11	5*	5*	3	.75	Tile	1.4	16	115	
8	Kitchen	70	11	0*	5*	3	.75	Larch Pine	1.8	20	140	
9	Main Room	70	11	41	5*	3	.75	Larch Pine	1.8	41	140*	
10	Upper Bath	70	11	41	5*	3	.75	Pine + Plank	2	33	140*	
11	Loft	70	11	41	0*	3	.75	N/A	N/A	27	140	
12	Bed 1	70	11	41	0*	3	.75	N/A	N/A	31	140	
13	Bed 2	70	11	41	0*	3	.75	N/A	N/A	31	140	
Out	Outdoor Design Temperature: -10 Deg. F. Total HeatLoad w/o DHW: 75kBTUs/hr											

Explanation of Terms : Performance Specs

Rm. #: The Room Number as listed on the Tubing layout, if applicable

Room Name: The Room Name

Room Temp: The maximum expected setpoint temperature for this room

Wall R .: The required R-Value of any outside walls

Ceil. R.: The required R-Value of the ceiling. * Indicates heated space above

SbFI. R.: The required R-Value under the floor. * Indicates heated space below.

Win R.: The required R-Value of any windows

ACH: The expected Air Changes per Hour in this space

Flooring Type: The exected finished flooring for this area

Floor R .: The R-value of the floor and subfloor assembly between the tubing and the living space.

BTUS S.F. The BTUS per square foot per hour required to heat the space under design conditions.

Water Temp: The Maximum water temp required to heat the space under design conditions.

* indicates Supplementary Heat source is used.

Loop Schedule								Plate Counts		
Man. #	Loop #	Zone	Install. Type	Tube Type	Loop Length	Cut List	Loop Bal.	Flow		9" W
M1	L1	1- Garage	Slab Below Grade	1/2" Hepex	300	1000' #1	8	.79	0	0
M1	L2	1- Garage	Slab Below Grade	1/2" Hepex	295	300 A	8	.94	0	0
M2	L3	2- Family Room	Slab Below Grade	1/2" Hepex	285	300 B	7	.48	0	0
M2	L4	2- Family Room	Slab Below Grade	1/2" Hepex	330	1000' #2	8	.83	0	0
M2	L5	2- Family Room	Slab Below Grade	1/2" Hepex	215	1000' #2	5	.54	0	0
M3	L6	3- Master Suite	Underfit Plates	1/2" Hepex	240	1000' #1	8	.67	88	0
M3	L7	3- Master Suite	Underfit Plates	1/2" Hepex	245	1000' #3	8	.69	82	0
M3	L8	3- Master Suite	Underfit Plates	1/2" Hepex	220	1000' #1	7	.54	72	0
M3	L9	3- Master Suite	Towel Warmer	1/2" Hepex	45	1000' #2	2	1.00	0	0
M4	L10	4- Main Room	Underfit Plates	1/2" Hepex	275	300 C	8	.54	100	0
M4	L11	4- Main Room	Underfit Plates	1/2" Hepex	260	1000' #3	7	.64	85	0
M4	L12	4- Main Room	Underfit Plates	1/2" Hepex	225	1000' #1	6	.55	65	0
M4	L13	4- Main Room	Underfit Plates	1/2" Hepex	210	1000' #3	6	.52	66	0
M4	L14	4- Main Room	Underfit Plates	1/2" Hepex	210	1000' #3	6	.52	65	0
M4	L15	4- Main Room	Underfit Plates	1/2" Hepex	225	1000' #2	6	.55	80	0
M5	L16	5- Upper Bath	Radiant Wall	1/2" Hepex	65	1000' #2	8	.45	0	16
M5	L17	5- Upper Bath	Towel Warmer	1/2" Hepex	25	1000' #2	3	1.00	0	0

Explanation of Terms : Loop Schedule

Man. #: The Manifold Station this Loop attaches to. Single loops are direct connections to the Mech Room Loop #: Loop Number

Zone: The zone this loop services

Install. Type: The radiant installation method used for this loop

Tube Type: The brand and diameter of the tubing used for this loop

Loop Length: The expected linear length of this loop. This number should be field verified for any major deviations. Cut List: The specific roll of tubing to cut this loop from. Mark tubing rolls prior to cutting to minimize waste!

Loop Bal .: The number of OUARTER turns from CLOSED to set this loop's balancing valve. 2 full turns is full open. Flow: The minimum GPM required by this loop under design conditions. ASSUMES 30% GLYCOL SOLUTION.

Installation Notes

In Slab Areas:

Before laying tubing it is a good idea to spray paint the outline of internal partition walls on the rigid foam as a guideline while running tubing. IF tubing passes under walls, NO masonry nails should be used to affix wall plates. Use of construction adhesive in such areas is recommended.

-Slab installations use the "full round" PVC bend supports for the tubing connection to the manifolds.

-Do not install splices in concrete if it is avoidable.

-Instructions for tubing installation around control joints, expansion joints and construction joints are in the Wirsbo installation manual chapter 8.

Manifolds mounted near the controls location do not require a valve on the manifold itself. Isolation occurs at the controls piping.

Underfit Plate Notes:

-Joist penetrations for tubing should be 1-1/2" in diameter near any bends in the tubing, 1" minimum for "straight shot" penetrations. Drill them prior to tubing installation.

-Feed the tubing through the supply penetrations and back through the return penetrations, and affix one end to the manifold. Leave the other end loose, leading to an uncoiler or an assistant. Then, starting at the furthest bay, pull the loose end up the joist bay and give the loop a 180 degree twist to make an expansion loop. Hook the tubing around an angled nail or use a tube talon to hold the tubing loosely in place while you continue this process for each joist bay in the loop. A diagram of this process is in the wirsbo installation manual, page 59. This process may have to be modified in areas where tubing must penetrate solid blocking.

This installation uses 5-3/4" wide plates 8" o.c. in the joist bays. Plates should never touch or overlap. Use the sample plate layouts as a guideline for plate installation density.

-Use at LEAST ten staples per plate. Plate must be as flat against the subfloor as possible to be effective. Use additional staples to ensure contact if the plates bow out away from the subfloor.

-Plates can be by scoring them with a utility knife, then snapped over a knee or a hard corner.

-Do NOT affix the head of the loop bends! Bend heads must be able to expand and contract with the tubing to prevent noise. Always leave 6" from the head of a loop to the end of joist bay insulation to give room for expansion.

-Underfit installations use the smaller nylon bend supports for the connection of loop tubing to the manifolds.

-All joists must be insulated, as specified in the performance specs on this page, under the plates. Where multiple zones share the same joist bay, the zones should be separated by some form of insulation.

Manifold/Feed Schedule

Man.	# of	Valve	Feed Tubing	GPM	Feed	Loop	Feed	Tot.
#	Loops	Operators	_		Length	Press	Press	Press
M1	2	None	3/4" Hepex	1.7	5	10.9	.1	11.0
M2	3	None	3/4" Hepex	1.9	90	10.5	2.2	12.7
M3	4	None	3/4" Hepex	2.9	5	5.1	.7	5.8
M4	6	None	3/4" Hepex	3.3	95	3.1	6.1	9.2
M5	2	None	3/4" Hepex	1.5	100	0.84	1.5	2.3

Explanation of Terms : Manifold Schedule

Man. #: The Manifold Station Number. Single loops indicate a direct connection is present, see loop schedule.

of Loops: The number of loops attached to this manifold station

Valve Ops.: The number/type of any mechanical valve operators on this manifold

Feed Tubing: The type and diameter of the tubing used to feed this manifold

GPM: The minimum flow rate required by this manifold under design conditions Feed Length: The expected total length of supply and return for this manifold's feed lines

Loop Press: The Pressure Loss of the longest loop on this manifold in Feet of Head. ASSUMES 30% GLYCOL SOLUTION. Feed Press: The Pressure Loss of the feed lines of this manifold in Feet of Head. ASSUMES 30% GLYCOL SOLUTION. Tot Press: The Total Pressure Loss on this manifold in Feet of Head. ASSUMES 30% GLYCOL SOLUTION.




contact Robert Brown For questions or changes regarding this page

Robert Brown nrt@maine.rr.com 207.899.2328 David Michaud nrtech@adelphia.net 207.582.8721


Gordon McAlister Radiant Floor Heating System Job #0304-05

Schedules, Specs, Installation Notes; Page 2 of 6, Revision Original, Drawn on 4/16/04



Slab Tubing Layout, Key To Symbols; Page 3 of 6, Revision Original, Drawn on 4/16/04

Robert Brown nrt@maine.rr.com 207.899.2328 David Michaud nrtech@adelphia.net 207.582.8721




NORTHEAST RADIAN T

TECHNOLOGY, L.L.C


Radiant Wall Detail For Upper Bathroom

Radiant Wall Installation Notes:




Gordon McAlister Radiant Floor Heating System Job #0304-05

First and Second Floor Tubing Layouts, HydroAir Feed Schedule; Page 4 of 6, Revision Original, Drawn on 4/16/04




Propex System Details; Page 5 of 6, Revision Original, Drawn on 4/16/04

nrt@maine.rr.com 207.899.2328 David Michaud nrtech@adelphia.net 207.582.8721



Controls and Piping; Page 6 of 10, Revision A, Drawn on 10/15/04

David Michaud dave@NRTradiant.com 207.582.8721



Note: The 063 RTU is to be configured for both slab and air sensing by using a 10k slab sensor connected to Ra3 and Com terminals (3 & 5) and the air sensor in 82P 88Åimum and max 80 slab temperatures and the air temperature settings are adjusted at the RTU. The minimum and maximum slab setpoints have priority over the air temperature setpoint. If the air temperature sensor at the RTU is turned off, the air temperature is ignored.

Note: The 063 RTU comes with four Access Level settings. These Access Level settings restrict the number of control settings retards that can be accessed by the user. The four access levels are Limited (LTD), User (USER), Installer (MIST) and Advanced (ADV). The access level of the RTU is found in the miscellaneous (MISC) menu. The control's factory setting is installer (MIST). Once the control is so tup, the appropriate access level is should be selected for the people that deal with 18 $\times A$ 8E0 a regular b 8:. One important feature of the RTU there is only a ± 9°F adjustment of the room temperature setting in the limited (LTD) access level. This feature can be particularly useful to limit tampering and unwanted temperature adjustment by children and others.

Note: The 352 control comes with four Access Level settings. These Access Level settings restrict the number of control settings that can be accessed by the user. The four access levels are Limited (LTD), User (USER), Installer (INST) and Advanced (ADV). The access level of the control is found in the Miscelaneous (MISC) menu when the Lock/Unlock DIP switch is set to the unlocked position. In the Advanced access level, all the control settings are available to the user. In the User access level, only a few of the menus and items are available. The control's factory setting is Installer (INST). Once the control is set up, the appropriate access level should be selected for the people that deal with the control

on a regular basis. The Lock/Unlock DIP switch is used to lock the access level of the control and RTU. To determine if the control is locked a small segment representing a padlock is viewed in the bottom right hand corner of the display. As long as the DIP switch is in the locked position, the access level of the control and RTU can no longer be viewed or adjusted in its Miscellaneous (MISC) menu.



contact David Michaud . For questions or changes regarding this page .

30 Sec.

Inst

362 DIP Settings

None Heat Curv

Misc Menu

ltem Field

Units

Backlight

Access

םו∎ר

Gordon McAlister Radiant Floor Heating System Job #0304-05

Controls and Wiring diagram (1 of 3); Page 7 of 10, Revision A, Drawn on 10/15/04

www.NRTradiant.com Rober

Robert Brownrob@NRTradiant.com207.899.2328David Michauddave@NRTradiant.com207.582.8721

362 Essential Settings

Adjust Menu

Setting

1(Heating)

70°F

None

HRF2

OFF

70°F

140°F

-20°F

150°F

VAR

None

65°F

Item Field

Mode

Room

Terminal

Mix Min

Mix Indoor

Mix Design

Mix Max


Mixing

Boil Sens

WWSD occ

OutDr Design


10k



Controls and Wiring diagram (2 of 3); Page 8 of 10, Revision A, Drawn on 10/15/04


www.NRTradiant.com Robert

Robert Brownrob@NRTradiant.com207.899.2328David Michauddave@NRTradiant.com207.582.8721



Controls and Wiring diagram (3 of 3); Page 9 of 10, Revision A, Drawn on 10/15/04

David Michaud dave@NRTradiant.com 207.582.8721



Future Chiller Installation Detail; Page 10 of 10, Revision Original, Drawn on 10/15/04

TECHNOLOGY, L.L.C www.NRTradiant.com

rob@NRTradiant.com 207.899.2328 Robert Brown David Michaud dave@NRTradiant.com 207.582.8721